
# Typical Screen Specification: Un wired, non insulating glass.

## FD30



# FD60

#### FD60 SPECIFICATION

Perimeter members: Thickness 44mm x minimum 75mm width.
Transoms / Mullions: Thickness 54 x minimum 75mm width.
Perimeter framework, transoms & mullions - Mortice & tennon jointed

Timber Grade :- Minimum density 550 kg/m³. Equal to or exceeding class J30 as specified in BS EN 942: 2007

Timber Type :- Hardwood. Species as noted in Y.D. schedule.

EXTENSION LININGS: - (Supplied in loose lengths to max three metres)
Paint Grade: - MDF, rebated to suit groove in perimeter framework, finished as lining.

Hardwood for Clear Finish - Edged with Hardwood lipping & faced with Hardwood veneer - Species & finish as lining.

ARCHITRAVES: -Supplied in loose lengths (If required) Details - As Y.D. typical frame detail drawing.

DECORATIVE UNDER COATS:- (Finishing coats to be site applied following installation).

Paint Grade: Linings, stops & architraves - One coat of white water based prime Clear Finish: Linings, stops & architraves - One coat of clear water based sealer.

Certification : BWF Certifire.

Certification: But Certific.

Fire Glazing Seals: Glazing tape (Supplied in loose reels). Colour - Black.

Glazing Beads: Section as below, mitred & shrink wrapped in place: Species & Finish: As perimeter framework.

Glass Type: Internal grade, 12mm un wired, EN410 86%, Ug value (EN673) 5.6W/(m².K), EN12600 2B2, EN12758 36dB. Glass Supply: Supplied loose to site following screen installation.


Bead Fixing: Bead filling / countersinking - on site by others
Bead Fixing: Either 60mm steel screws fixed at 200mm centres (30° to glass). Not supplied with screens.

Bead Fixing: Or 60mm steel pins fixed at 150mm centres (30° to glass). Not supplied with screens

### DELIVERED

For 2016

embled. Detached from door frames (See abutment drawing below)



### Glazing Beads

Timber species : As screen members
Section : As above or square section (27 x 32mm)
Supplied : Beads supplied mitred & shrink wrapped in place.
FD60 Fixings : As above specification.
(Note : Fixings, setting blocks, drilling & countersinking by glaziers)

